BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT35736

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2019-20, Date: 14.05.2019

Improvements to drains of Vayunandhan Layout Cross roads in Kempapura in ward no.07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRAKASH NAIK ( )	
				In Figures	In Words
1	297.83	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.143.Item No.19.1)	Cum	145.0	Rupees One Hundred Forty Five Only
2	45.5	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.13, It.4.3)	Cum	5678.0	Rupees Five Thousand Six Hundred Seventy Eight Only
3	606.6	Providing granite slabs of selected quality reoughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5cms thick(Pg No.27, Item No.5.31.1)	Sqm	779.0	Rupees Seven Hundred Seventy Nine Only
4	1066.2	Providing granite slabs of selected quality reoughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 10cms thick (Pg No.27, Item No.5.31.2)	Sqm	1015.0	Rupees One Thousand Fifteen Only
5	161.46	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	2337.0	Rupees Two Thousand Three Hundred Thirty Seven Only
6	12	KSRRB M2900-2.1. Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300 Page No. 255, Item No. 34.7.8, PWD SR 2018-19	Mtr	6274.0	Rupees Six Thousand Two Hundred Seventy Four Only
7	1.36	Providing 100mm and down size nominal size. (Pg No.I.Item No.23)	Cum	1037.0	Rupees One Thousand Thirty Seven Only
8	0.9	Providing 40mm and down size nominal size (Pg No.II.Item No.25)	Cum	1146.0	Rupees One Thousand One Hundred Forty Six Only
9	0.9	Providing 20mm and down size nominal size (Pg No.II.Item No.28)	Cum	1146.0	Rupees One Thousand One Hundred Forty Six Only
10	0.68	Providing Fine aggrgate 2.36mm nominal size (Pg No.II.Item No.32)	Cum	1107.0	Rupees One Thousand One Hundred Seven Only
11	297.83	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 136, item No. 17.1)	Cum	98.5	Rupees Ninety Eight and Fifty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

28/06

28/06